



GUAM WATERWORKS AUTHORITY

Gloria B. Nelson Public Service Building • 688 Route 15, Mangilao, Guam 96913 • Tel. (671) 300-6036

NOTIFICATION

This is a notification for two upcoming projects under the Guam Water and Wastewater Infrastructure Improvements Program. The Guam Waterworks Authority (GWA) is inviting interested Contractors (“Bidders”) to participate in two Bids for construction services as described below:

1. The Northern Guam Lens Aquifer (NGLA) Monitoring System Expansion Project (Expansion); and
2. The NGLA Monitoring System Rehabilitation Project (Rehabilitation)

Bids for the Expansion project will provide complete construction services for the installation of seven new monitoring wells and rehabilitation for two existing monitoring wells on Department of Defense (DoD) property. Bids for the Rehabilitation project will provide complete construction services for the rehabilitation of ten existing monitoring wells located on GovGuam or private property. Upon construction completion, all wells will be used to monitor water level and other groundwater characteristics of the NGLA.

Because the construction requirements (i.e. access badges, notifications, etc.) differ between wells located on DoD Property and those not located on DoD property, the two Construction Bid Packages will be issued separately to accommodate these differences as follows:

- A. The NGLA Monitoring System Expansion Project: This bid package will include installation of seven new monitoring wells and rehabilitation for two existing monitoring wells on DoD property. The new monitoring wells will be constructed using the air rotary drilling method. The new monitoring wells’ completion depths will range from 500 to 800 feet, depending on the site. All new wells will be constructed with 6-inch-diameter Schedule 80 flush-threaded PVC blank casing and well screen. New and existing wells will require ground level wellhead completion, which includes but is not limited to concrete pads, locking well caps, wellhead cabinets, and security fencing. The rehabilitation activities also include demolition of existing concrete and fencing, where necessary.
- B. The NGLA Monitoring System Rehabilitation Project: This bid package will include rehabilitating the remaining ten existing monitoring wells. These ten wells are not located on DoD Property. The intent of the project is to perform rehabilitation activities on each monitoring well to help prolong the life of each facility. Existing wells will require ground level wellhead completion, which includes but is not limited to concrete pads, locking well caps, wellhead cabinets, and security fencing. The rehabilitation

activities also include demolition of existing concrete and fencing and removal of vegetation where necessary. For some of the existing wells removal of debris, removal and replacement of PVC casing, and new filter material will be required.

It is anticipated that the Invitation to Bid for these packages will be advertised by mid-January 2020. We appreciate any interest you may have in providing a bid on these upcoming packages. Please carefully watch Guam Waterworks Authority's website at <http://guamwaterworks.org/bid/> for future bidding details.

Sincerely,



MIGUEL C. BORDALLO, P.E.
General Manager