



GUAM WATERWORKS AUTHORITY

Should you have questions or concerns,  
please call GWA's 24/7 Water Line at 646-4211  
or email [heidi@guamwaterworks.org](mailto:heidi@guamwaterworks.org).



# GWA SYSTEM IMPROVEMENT PROJECT

## What is GWA doing? – Sewer Rehabilitation work along Marine Drive in Hagatña.

The Project is the Rehabilitation of the Existing Sewerline from Asan (*located 1,000 feet to south of Governors Complex Gate*) to Hagatña Wastewater Pump Station (*located at the Chamorro Village, near Fisherman Coop.*) – The work consists of cleaning and rehabilitating existing 16-inch, 24-inch and 27-inch diameter gravity sewer lines with Cured-In-Place Pipe (CIPP) liner, reinstating sewer laterals after CIPP rehabilitation is complete, replacing sewer manhole concrete collars, and providing temporary bypassing and traffic control as necessary to complete the rehabilitation work. The work also includes installing a new 12-inch diameter Polyvinyl Chloride (PVC) sewer line from Asan (*Right in front of Mobil Gas Station, R1-R6 Crossing*) to a sewer manhole in Asan (*Located in the centerline of Route 1-Route 6 Crossing*) and providing temporary bypassing and traffic control as necessary to complete the work.

**Traffic Control:** The Contractor will adhere to the traffic control approved by DPW. The contractor will also provide road ramps over bypass piping as shown on the maps, channelizing devices, signs, and barricades in accordance with the requirement of DPW. Contractor will provide a minimum 10 feet wide traffic lanes. Driveways shall be kept open and if access closure is needed, the contractor will provide prior notice of alternative access. Contractor will provide signs to direct traffic in and out of driveways.

**Project Timeline:** May 15, 2021 – April 2023

**System Improvement Location:** See Attached Map

### **Contact Person for GWA:**

**Heidi M. Ballendorf**  
Communications Manager  
687-4505

**Contractor:**  **Core Tech - Hawaiian Dredging, LLC** 

**Lerny Leonardo Abayon**  
Project Manager - CHL  
685-1135