



Gloria B. Nelson Public Service Building 688 Route 15 Mangilao, Guam 96913 | (671) 300-6058

**Aplacho Sewer Pump Station Drainage and Roadway Improvements GWA**  
**GWA Project No. S22-03-BND**  
**IFB-02-ENG-2022**  
**GWA RFI Response Nos. 1 and 2 to Contractor Inquiries**

This Addendum and/or Response to Request for Information (RFI) is issued to modify the previously issued bid documents and/or given for informational purposes and to the extent the responses below modify the bid documents, please treat them as an amendment to the Bid. The following are responses to RFIs received:

NO.	DATE	QUESTION/INQUIRY AS SUBMITTED	GWA RESPONSE
<b>Questions from June 20, 2022</b>			
1		<p>“On the Unit Price Bid Form kindly clarify which scope belongs to Item 7 Road Reconstructions and which belongs to Item 8 Road Resurfacing?</p> <p>7. Road Reconstruction (including saw cutting, removal of pavement, sub-grade prep/compaction, subbase, aggregate, tack coat, and pavement)</p> <p>8. Road Resurfacing (including saw cutting, removal of pavement, subgrade, prep/compaction, subbase, aggregate, tack coat, and pavement)”</p>	<p>Item No. 7: Road reconstruction to be from Station 27+10 to Station 30+00 due to the road on going deterioration.</p> <p>Item No. 8: Delete Road Resurfacing.</p> <p>See Addendum 01.</p>
2		<p>“On the Unit Price Bid Form, kindly clarify Item 10 tack coat/prime coat will be the priced for 1" thick hot asphalt concrete friction course and exclude the 3" thick hot asphalt concrete pavement.”</p>	<p>Delete Tack Coat/Prime Coat. See Addendum 01.</p>



## GUAM WATERWORKS AUTHORITY

Gloria B. Nelson Public Service Building 688 Route 15 Mangilao, Guam 96913 | (671) 300-6058

### Questions from July 12, 2022

1		<p>"The IFB states that the contract duration for the project is 155 days, kindly confirm that this is after the processing of all the necessary permits."</p>	<p>Refer to the Agreement Between Owner and Contractor for Construction Contract in Section 00520, Article 4, paragraph 4.02 on Contract Times: Days</p> <p>"The Work for Base Bid will be substantially completed within <b>155</b> calendar days from Notice to Proceed issuance as provided in Paragraph 4.01 of the General Conditions, and completed and ready for final payment in accordance with Paragraph 15.06 of the General Conditions within <b>185</b> days after the date when the Contract Times commence to run."</p> <p>Contractor shall achieve substantial completion within 155 calendar days, which shall include processing and obtaining all necessary permits.</p> <p>Any claims for the adjustment of contract time shall comply with Section 00700, Article 11, paragraph 11.05, Change of Contract Time.</p>
2		<p>"We would like to confirm that in the 'Resurfacing' segment of the project, if it is possible that we fully remove the existing asphalt pavement and make the section same as the "Reconstruction" segment per plan?"</p>	<p>Road reconstruction to be from Station 27+10 to Station 30+00 due to the road on going deterioration.</p> <p>Delete Road Resurfacing.</p> <p>See Addendum 01.</p>



## GUAM WATERWORKS AUTHORITY

Gloria B. Nelson Public Service Building 688 Route 15 Mangilao, Guam 96913 | (671) 300-6058

3		"Under project specification Section 156.06 (I), can you please clarify the removal of traffic signs and devices during non-construction operation. This may be hazardous especially at night if we happen to start excavating. From our site visit, all vehicles passing through the job site are speeding up. Note, the jobsite area is curve and prone to accident."	Temporary signs and traffic devices shall be removed from the travel way when they are not in use. If the temporary signs and traffic devices are needed during non-construction hours for the safety of the public, then they shall remain in place and be visible to the motorists.
4		"During the site visit we were unable to identify the location of the fire hydrant as per plan. Can you please indicate the existing fire hydrant and the proposed location."	The fire hydrant has already been removed. Hydrant work is not in contract. See Addendum 01.

Bidders are also notified to visit GWA website: <http://guamwaterworks.org/bids/> to ensure that addenda to the bid, answers to questions, and reminders are communicated to all bidders throughout the solicitation process.

MIGUEL C. BORDALLO, P.E.  
General Manager

cc: MCB, RAC