

GUAM WATERWORKS AUTHORITY
Gloria B. Nelson Public Service Building | 688 Route 15, Mangilao, Guam 96913
P.O. Box 3010, Hagåtña, Guam 96932
Tel. No. (671) 300-6846/48 Fax No. (671) 648-3290

Deep Wells D-17, Y-15, and M-4 GAC System Dieldrin Treatment IFB-04-ENG-2024 GWA Project No. 12309 GWA Response to RFI No. 2 to Contractor Inquiries

This Addendum and/or Response to Request for Information (RFI) is issued to modify the previously issued bid documents and/or given for informational purposes and to the extent the responses below modify the bid documents, please treat them as an amendment to the IFB. The following responses are in response to RFIs received.

	DATE	QUESTION/INQUIRY AS SUBMITTED:	GWA RESPONSE:
1	03/28/2025	Could you please confirm whether "Notit GAC 400" (attached) can be used as a substitute for "FILTRASORB 400M" or "TIGG 5D 0830 NSF" or "5D 1240 HM," as specified in Part 2, Paragraph	Bidders shall follow the product requirements of Section 460101, Part 2.1.
		2.1.a (Page 414 of 443)? Per the specifications, approval is required prior to submitting the bid. If necessary, a sample can be provided to GWA.	Approved substitution or equal material may be considered after award. Considering bid timing section 2.1.a.a.i has been updated as follows:
			"Approved equal products (substitution) must be approved by the engineer/owner prior to order. A rapid small-scale column testing (RSSCT) by a third party testing facility shall be performed and results provided to the engineer/owner as part of this request."
2	04/01/2025	Please provide specification and vessel sizes for GAC system at	Refer to sheet 3 of 22 / MP-1.2 of plan set. 12 ft. – 2 in. diameter,
		the well Y15. Drawing C2.2 shows two new GAC systems.	18 ft. high coated steel and Specification Section 434221.
		Drawing M2.2 is a schematic and does not provide vessel sizes.	
3	04/01/2025	Please provide vessel sizes at well sites A08 and F08.	Relocated vessel sizes are 8 ft. diameter 12 ft. high and 8 ft. diameter 9 ft. – 4 in. high, respectively. These vessels are to be relocated to D-17 and M-04; see notes on Plan Sheets 2 & 4 of 22 / MP-1.1 & MP-1.3.
4	04/02/2025	Please advise if this project is covered under the Multi-Agency	This project has a BABA waiver.
		Pacific Island Territory BABA Waiver, which was approved on January 8th for the US Pacific Island Territories.	

Bidders are also notified to visit GWA website: www.guamwaterworks.org/bids to ensure that addenda to the IFB, answers to questions, and reminders are communicated to all bidders throughout the solicitation process.

Christopher M. Budasi Acting General Manager