



GUAM WATERWORKS AUTHORITY
 Gloria B. Nelson Public Service Building | 688 Route 15, Mangilao, Guam 96913
 P.O. Box 3010, Hagåtña, Guam 96932
 Tel. No. (671) 300-6846/48 Fax No. (671) 648-3290

IFB No. 2026-29
Road Restoration Services
Response for Inquiries No. 2

This document addresses inquiries regarding IFB 2026-29. It provides clarifications and additional information for informational purposes. In the event that any responses result in modifications to the bid documents, they should be considered as amendments to the original IFB 2026-29.

I. NOTICE TO PROSPECTIVE BIDDERS:

- a. IFB No. 2026-29, Scope of Work (Page 7) shall be amended and replaced with the following:

Scope of Work (REVISED)

Locations Included & Measurements:

Location:	Measurement:
1. Barrigada Tri-Intersection	Flowable fill: 156" x 65" Asphalt repairs: 22'L x 11'W'
2. Rt. 10 Barrigada (Near Uncle Cho's Mart)	Flowable fill: 80" x 66" Asphalt repairs: 10'L x 11'W'
3. Rt. 10 Mangilao (After Rt. 10 / Rt. 15 Intersection, Heading towards Barrigada)	Flowable fill 7.'L x 7.5'W Asphalt 3 7.5'L x 7.5'W Friction course 1" 7.5'L x 11'W
4. Rt. 10 Mangilao After entrance to Lalo Street	Flowable fill 5.5'L x 5.5'W Asphalt 3" 5.5'L x 5.5'W Friction course 1" 5.5'L x 11'W
5. Rt. 10 Barrigada (Across Puff Supply)	Flowable fill 9'L x 5'W Asphalt 3" 9'L x 5'W Friction course 1" 9'L x 11'W



GUAM WATERWORKS AUTHORITY
 Gloria B. Nelson Public Service Building | 688 Route 15, Mangilao, Guam 96913
 P.O. Box 3010, Hagåtña, Guam 96932
 Tel. No. (671) 300-6846/48 Fax No. (671) 648-3290

II. Responses to Questions received by August 21, 2026, are as follows:

QUESTION/INQUIRY AS SUBMITTED:	GWA RESPONSE:
1. With regards to building and encroachment permits, we would like to recommend that GWA work with DPW to waive the permits to eliminate costs that will be incurred and save time needed in applying for the building and encroachment permits. Please note, applying for a building permit will require complete set of drawings and specifications stamped by a professional engineer. Please advise.	Your request is noted. Please refer to Scope of Work (page 7) as amended in Section I of this document. Work to be performed in accordance with Guam Waterworks and the Department of Public Works Standards. Contractors are responsible for Highway Encroachment Permits and associated traffic plans. GWA will work with DPW to expedite.
2. From our previous and current federal projects with DPW, work is not allowed during peak travel periods during the normal work week (Monday through Friday), between the hours of 6:00 a.m. and 9:00 a.m. and between 4:00 p.m. and 6:00 p.m. Since all the work on this IFB is on federal roads, we are assuming the same restrictions. Please advise.	Contractors shall follow all DPW requirements for road closures.
3. On the second site visit conducted on August 21, 2026, GWA personnel mentioned that the areas on Route 8 will only be road resurfacing. Please confirm if this means milling or removal of existing 4" thick asphalt pavement and replacing it with 3" thick of minor asphalt pavement and 1" thick of friction course.	Responses during the site visit are unofficial. GWA maintains the Scope of Work as described in Section I. Notice to Prospective Bidders, a. Scope of Work (page 7) as amended in Section I of this document.
4. Attached is a drawing with road repair dimensions for Route 8. Please advise if we can use these dimensions as basis for our bid.	The dimensions to be used as the basis of bid are those shown in the Scope of Work as amended by Section I of this document. Bidders shall not rely on drawings or dimensions not issued by GWA as part of this solicitation.
5. Please confirm that Water Valve (WV) Box and Sewer Manhole (SMH) Frame and Covers will be supplied by GWA if there is any WV and/or SMH frame and cover adjustment.	GWA will provide the Sewer Manhole (SMH) Frame and Covers.



GUAM WATERWORKS AUTHORITY
 Gloria B. Nelson Public Service Building | 688 Route 15, Mangilao, Guam 96913
 P.O. Box 3010, Hagåtña, Guam 96932
 Tel. No. (671) 300-6846/48 Fax No. (671) 648-3290

QUESTION/INQUIRY AS SUBMITTED:	GWA RESPONSE:
6. May we kindly request the measurement or approximate dimensions of the affected road area related to the project? Specifically, we would appreciate the length, width, and total area (SF) of the portion of the road that will be affected.	Please refer to I. Notice to Prospective Bidders, a. Scope of Work (page 7) and as amended in Section I of this document.
7. May we kindly ask for clarification regarding the affected road area. Could you please confirm whether the road marking works are included in our scope of work?	Please refer to Scope of Work, 5. Pavement Markings/Striping (Page 7).
8. During the first site visit, GWA stated that only the disturbed area will receive the 3ft flowable fill and the remaining area of the lane width will have 3" thick minor asphalt and 1" friction course to satisfy DPW requirement. On the Responses to Inquiries No. 1, Items 5 and 12, dimensions were provided for 5 locations, and it seems that the width is 11 feet for all locations. Does this mean that the whole lane width will be excavated to 3ft-4inches and replaced with 3 ft thick flowable fill, 3" minor asphalt, and 1" friction course? For example, Item 5, number 1) Route 10 northbound outer lane near wall has dimension of 7ft x 11ft provided on the response. However, the actual width of the disturbed area on this location that needs flowable fill is only 7.5ft. Do we need to provide flowable fill on the 11" wide lane or the 7.5ft disturbed area?	Flowable fill should only be for the initial area that was excavated. The 3" asphalt should only be for the areas that were excavated or damaged. The overall dimensions should be 1" friction course for the lane.
9. We measured each disturbed area, and we got the ff. measurements: 1) Rt 10 Mangilao (After Rt 10/Rt 15 Intersection) Heading Towards Barrigada: 7.5'L x 7.5'W 2) Rt 10 Barrigada (Near Uncle Cho's Mart): 8'L x 8'W 3) Rt 10 Mangilao after entrance to Lalo: 5.5'L x 5.5'W	The disturbed areas will have both flowable fill and 3" thick minor asphalt, and the whole width of the lane will be 1" thick friction course.



GUAM WATERWORKS AUTHORITY
 Gloria B. Nelson Public Service Building | 688 Route 15, Mangilao, Guam 96913
 P.O. Box 3010, Hagåtña, Guam 96932
 Tel. No. (671) 300-6846/48 Fax No. (671) 648-3290

QUESTION/INQUIRY AS SUBMITTED:	GWA RESPONSE:
4) Rt 10 Barrigada (Across Puff Supply): 9'L x 5'W 5) Barrigada Tri-Intersection: 11'L x 22'W Please advise if you agree to use these dimensions that will receive 3' thick flowable fill and the whole width of the lane will receive 3" thick minor asphalt and 1" thick friction course.	

Bidders are also notified to visit the GWA website: www.guamwaterworks.org to ensure that any addenda to the bid, answers to questions, and reminders are communicated to all bidders during the solicitation process.

 Miguel C. Bordallo, P.E.
 General Manager

September 9, 2026